
## **CHAIN LINK FENCING DETAILS**



**APPROVED** 

ASSISTANT DEPUTY DIRECTOR

APRIL 2004

DATE

W-23

SHEET 1 OF 2

## **CHAIN LINK FENCING DETAILS**

## **GENERAL NOTES:**

- 1. INTERMEDIATE HORIZONTAL BRACES ON END, CORNER, ANGLE, AND PULL SECTIONS ONLY.
- FOOTINGS SHALL ENCASE BASES OF ALL POSTS BY A MINIMUM OF 4" ON ALL SIDES AND BOTTOM.
- 3. ABRASIONS TO GALVANIZING SHALL BE TOUCHED UP WITH GALV (ZINC) PAINT.
- 4. BARBED WIRE REQUIRED ON ALL SECTIONS AND ON GATES, EXCEPT WHEN DELETED ON PLANS OR IN SPECIFICATIONS CONFORMED TO THE STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION (LATEST EDITION) 206-6-6.7 AND ASTM-A121.
- 5. BARBED WIRE IS NOT REQUIRED ON GATES WHEN NOT REQUIRED ON FENCING.
- 6. ALL GATES SHALL BE EQUIPPED WITH LOCKING CHAIN.
- ALL END, CORNER, ANGLE, AND PULL POSTS SHALL HAVE MINIMUM BURY IN CONCRETE OF 36".
   ALL LINE POSTS SHALL HAVE 30" BURY.
- 8. DRILL AND PIN OR RIVET ALL CAPS (EPOXIED CAPS ARE ACCEPTABLE).
- ALL GATES 6' HIGH SHALL HAVE 2 HINGES MINIMUM, AND ALL GATES 8' HIGH SHALL HAVE 3
  HINGES MINIMUM.
- 10. MATERIALS FOR POST, RAILS, AND BRACES SHALL CONFORM TO THE STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION (LATEST EDITION) TABLE 206-6.2 (A).
- 11. REPAIR OF DAMAGED COATING OF GALVANIZED SUFACES SHALL BE CLEANED AND PAINTED WITH ZINC RICH PAINT SUCH AS GALVICON OR GALVALLOY OR APPROVED EQUIVALENT.

LOS ANGELES COUNTY WATERWORKS DISTRICTS

DEPARTMENT OF PUBLIC WORKS

STANDARD PLAN

W-23

SHEET 2 OF 2

**APPROVED** 

ASSISTANC DEPUTY DIRECTOR

APRIL 2004

DATE